BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED TENDER SCHEDULE –'B'

Name of Work:-Construction of drains at 1st main 4th cross Maruthinagara (ST colony) in ward No-01 of Yelahanka Sub Division

Sl	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
1	**Removing B.S. slab** of Drain and stacking.(P No.25 / I N 5.32)	Sqm	202.50	66.96	Rupees sixty six and paise ninety six only
2	KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH Chapter 3 (P.142/I.19.1)	Cum	91.80	88.56	Rupees eighty eight and paise fifty six only
3	KSRRB M200-24:- Dismantling of cement concrete pavement by mechanical means using pneumatic toos, breaking to pieces no exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials upto a lead of 000 meters stacking serviceable and unserviceable materials separately complete as per specification MORTH spcifications No 202 (P.No 138/ Item No 18.47)	Cum	79.12	843.48	Rupees eight hundred forty three and paise forty eight only
4	KSRB 2-1.1 : Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1 (a) / 2.3.1 (P.5/I.2.1)	Cum	79.12	169.56	Rupees one hundred sixty nine and paise fifty six only
5	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1)	Cum	250.04	100.00	Rupees one hundred only

...RAO K.)
Executive Director

BANGALORE

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
6	**Refixing stone slabs** of drains and pointing in C.M.(1:3)(P.No.25/I.No.5.33)	Sqm	162.00	82.08	Rupees eighty two and paise eight only
7	Providing and fixing **RCC precast Slabs of 0.10 m thick of CC 1:2:4 with 20 mm** and down size graded granite metal , machine mixed , including cost of all material , labour , HOM of Machinery , curing complete	Sqm	67.50	2100.00	Rupees two thousand one hundred only
8	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.1, 4.2 (P.12/I.4.3)	Cum	59.34	5256.36	Rupees five thousand two hundred fifty six and paise thirty six only
9	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)M20 for RCC works laid in 15cms thick layeres and well compacted vibrating, cutting for raft foundation column footing main and secondary beams with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges) Page No 18 Item 4.48	Cum	49.45	6349.32	Rupees six thousand three hundred forty nine and paise thity two only
10	Vaccum De- Watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery screed vibratiry, Power floater, blade and disc etc., with all lead and lift (P 177/1.22.7	sqm	395.60	97.20	Rupees ninety seven and paise twenty only
11	Providing Groove cutting for width of 5mm to 10mm and epth 80mm to 100mm including cost of cutting machine geerator and HOM of machinery including cost blade, coolant etc., including cleaning of groove & providing sand and hot bitumen fillars and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all the other incidental charges as per drawing and as per specifications, MORTH specification (P 178/1.22.8)	mtr	172.93	124.20	Rupees one hundred twenty four and paise twenty only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.

ecutive Director